

**Givaudan**®  
Leading Sensory Innovation




## Convention on the Transboundary Effects of Industrial Accidents

November the 26th, 2008

## Givaudan leader of the fragrance and flavour market


Sales 2007 market share in percent



Worldwide market  
CHF ~17-18 billions


Givaudan :  
Sales of CHF ~4.2 billions

## Givaudan, leader of the sensory innovation



Givaudan®

## Some of our customers



BDF ••••  
Beiersdorf

AVON

*Procter&Gamble*

  
**A FAMILY COMPANY**

 Bristol-Myers Squibb Company




L'ORÉAL


Present all over the world with 9000 people

Givaudan<sup>©</sup>

- < 200 employés
- 200 - 500
- > 500



## Driving industry consolidation and integrating a rich heritage ...




**Givaudan**  
Leading Sensory Innovation



**Givaudan in Geneva**

## The Geneva's plant is 110 years old

- Established by Léon Givaudan in 1898
  - 0.62 hectares rent to the city of Geneva
  
- 110 ans later
  - 22 hectares
  - 70 buildings
  - 850 employees (550 in Operations)
    - 347 union contracts
    - 397 individual contracts
    - 16 apprentices



Xavier Givaudan

## Activities on site

- Headquarters
  - CEO
  - CFO
  - Global informatics
  - Legal department
  - Human Resources
  - Communication and investor relationship
  - Global safety and environment
- Production of fragrance compounds
- Production of fragrance ingredients
- Ingredients global marketing
- Global operations for fragrance division



Major accident prevention : what has been done between 1972 and 2000

## Complete control of the water effluents

- Construction of a waste water treatment plant adapted to chemical manufacturing :
  - 1st step : chemical treatment (pH, solvent decantation, inorganic salts precipitation) (1972)
  - 2<sup>nd</sup> step : biological treatment (1982)
- Construction of a large retention basin able to contain the surface water and the water which might be used during fire fighting (4.5 hour retention). It was built after the Schweizerhalle accident

## **Givaudan is able to face incidents/accidents and reduce their impacts**

- A fire brigade specially trained for fire fighting, pollution containing and treating injuries
- Ambulance and 3 trucks also equiped to fight metal fires
- Crisis management
- Excellent contact and coordination with the authorities



**Major accident prevention : what has been  
done between 2000 and 2007**

## Study of the impacts of raw material storage


1. Software selection in coordination with the State of Geneva (Mr Susini)
2. Elaboration of 17 scenarios
3. Calculations / modelling
4. Implementation of action plan resulting from the scenario calculations

## Software selection

Software implemented : MERCURE from ARIA Technologies,  
developped by EDF

- This software is based on a 3D eulerian atmospheric dispersion model
- It takes into account :
  - The dynamic (wind field)
  - The temperature (gradient of temperature)
  - The microphysic of the fluid flow
  - The transportation of the pollutant by the wind
  - The turbulent diffusion of the pollutants
  - The formation of aerosols

## Data introduced into the system



## Scenarios

- List of the products identified as being stored in large quantities (the threshold quantities are given by the Swiss legislation) :
  - 54 products in 2007
- 17 scenarios chosen according to the following criteria:
  - Product toxicity
  - Flash point
  - Location on site
- Scenarios were discussed and approved by the State of Geneva

## Scenarios

Risks :


- Drum or tank leak
- Drum or tank explosion

Major accidents :


- Toxic product cloud (aerosol)
- Cloud inflammation + combustion products
- Tank explosion due to external events
- BLEVE (Boiling liquid expanding vapor explosion)

# **Final approach for each product**

## ■ Cause tree




## ■ Failure tree



## Final approach for each product

- Calculation with MERCURE
- Evaluation of the number of victims
- **Cumulative curve of criticality :**



## Action plan decided after the analysis – some examples (1)

- Doubling of the bottom valve for certain products  
(Hydrochloric acid for example)
- Reinforcement of risk analysis for the stored products and the chemical processes
- Review of the preventive maintenance frequency of certain equipments
- Use of this analysis inside the crisis management



**Major accident prevention : what is on going  
from 2008**

## New warehouse under 13 % oxygen atmosphere

- This warehouse will hold 80 % of the drums presently distributed all over the plant
- This new technique of reduced oxygen content atmosphere (4th warehouse of this type in Switzerland) prevents or stops fire of any product first tested under 13 %
- This technique also reduces the cost of the warehouse : no sprinkler equipment required

## Other actions

- Review all the chemical processes following 2 axes :
  - Detailed study of the thermodynamic conditions with a new hired expert
  - Comprehensive survey of the water cadastre (impact of the different synthesis on the waste water treatment plant)
- Establish a policy for the integration of the Safety integrity levels (SIL) in the design of new equipments

**Givaudan<sup>®</sup>**  
Leading Sensory Innovation