

Poverty Measurement During COVID: Administrative Records as Contrast and Data Source Results 2020

November, 2021



El futuro
es de todos

Gobierno
de Colombia

Agenda

- I Institutional Framework of the measurement for income poverty in Colombia
- II Information collection context for the Great Integrated Household Survey (GEIH) in 2020
- III Use of administrative records for the construction of the 2020 income variable
- IV Income poverty 2020: Main results

Institutional Framework: Income poverty measurement



**El futuro
es de todos**

**Gobierno
de Colombia**



CONPES 150 of 2012

Official methodologies and institutional arrangements for measuring poverty in Colombia


CONPES Recommendations:

- DANE will be responsible of the production and officialization of poverty figures: income poverty and multidimensional poverty.
- With the objective of guaranteeing the transparency, comparability and methodological stability of estimates, CONPES establishes the creation of a Committee of Experts on Poverty.
- The Committee will be coordinated by DANE with the participation of National Planning Department (DNP) and Social Prosperity Department (DPS).
- DANE, DNP y and the Committee members must keep total confidentiality of the information on income and multidimensional poverty until the moment the figures are made official by DANE.

Income poverty measurement methodology

Income Poverty and Extreme Poverty

Due to the availability of updated information on Colombians' consumption patterns in the National Household Budget Survey (ENPH) 2016-2017, DANE in collaboration with the Committee of Experts on Poverty conducted a methodological update of the extreme monetary poverty and income poverty lines.





Income source

The added income sources are the following:

- First Activity Income
- Second Activity Income
- Income in Kind
- Income Entry of the Unemployed and the Inactive
- Interest and dividends on investments (IOF1)
- Pensions and retirements (IOF2)
- Food and household assistance (IOF3H)
- Government Allowances (IOF3I)
- Leases (IOF6)


Information Collection Context of GEIH-2020



El futuro
es de todos

Gobierno
de Colombia

Chronology of events GEIH 2020



Enhancement of the GEIH with administrative records



El futuro
es de todos

Gobierno
de Colombia



Use of the GEIH survey and Administrative Records

Key notes

- ECLAC's Statistical Division suggests using Administrative Records (RRAA) to solve possible coverage biases, given the variations that may occur due to changes in collection operations. In this regard, DANE used administrative data as a source of contrast and imputation to minimize possible coverage biases in the income recovery operation, due to the time lag in the collection of information.
- Although the GEIH does not ask for mandatory fields of type and number of identity document since 2018, the completeness and consistency (evaluated with the REBP) of these fields allows linking the survey with different datasets.
- The integration of surveys with administrative records has the potential to improve precision and accuracy in the measurement of some income sources subject to possible coverage biases, non-response biases and measurement biases.
- For the 2020 exercise, 2019 was used as a counterfactual to assess the relevance of using administrative data. Therefore for 2019 and 2020, a coverage analysis was performed, which consisted of contrasting the value observed in the survey and the population value of administrative records; and a reporting bias analysis, based on the comparison between the income observed in the common population between the survey and the administrative data.

Methodology

GEIH and Administrative Records Integration

- For the construction of the First Activity Monetary Income (IMPA), the wages and net earnings reported in GEIH were used. For the period March-July 2020, in which the form was shortened and the operation was carried out by telephone, the other incomes that make up the IMPA could be estimated thanks to the income information recovery operation. Likewise, this source allows the construction of the information of ISA, IMDI, IOF1 (interest and dividends), IE (income in kind), IOF6 (effective rent).
- For income sources IOF2 (pensions) and IOF3I (government allowances), administrative records are used to enrich and complement the information reported in the survey:
 - Pensions (IOF2): the amount of the pension table reported in the PILA is used.
 - Government Allowances (IOF3I): the monthlyized amount of total collections observed in the "portability zone" of each individual during 2020 is used.
- Taking into account the structural shock on revenues caused by the COVID-19 situation for 2020, the sample splits for revenue imputation are as follows: January-February, March-July and August-December.


Administrative Records

Main geographic domains and 23 cities and Metropolitan Areas

Source	Administrative Record	Aid	GEIH question to be improved	2019	2020
Social Prosperity Department	Mas Familias en Acción (FA)	Ordinary Payment	P1661S1A1	X	X
		Extraordinary Payment			X
	Jóvenes en Acción	Ordinary Payment	P1661S2A1	X	X
		Extraordinary Payment			X
	Colombia Mayor (CM)	Ordinary Payment	P1661S3A1	X	X
		Extraordinary Payment			X
	VAT Compensation-CM	Payment	P1661S4A2		X
	VAT Compensation-FA	Payment			X
	Ingreso Solidario (IS)	Payment			X
	Bogotá's Townhall	Bogotá Solidaria		Payment	
Bucaramanga's Townhall	Bono vital Bucaramanga	Payment		X	
Medellín's Townhall	Medellín	Payment		X	
Health Ministry	Entidad Pensionados			X	X

Administrative data as contract and data source

Integration protocol between data sets



Source: DANE: CNPV 18, GEIH-18, RELAB-18. Prosperidad Social: More Families in Action (FA), 2018, Youth in Action (JA), 2018. DNP: Sisbén IV. Min. Educación: SIMAT-18.

Note: The Reference Dataset (RD) is a record that contains population information with full updated names, types and ID numbers, as well as other variables.

Administrative Records Quality Management

Input Protocol

1. Preparation of Admin. Records

- Cleaning of the variables in terms of existent invalid characters.
- Elimination of leading zeros in the identification documents.
- Variable enhancements.
- Verification of formats (i.e. dates), detection of default values.

3. Consistency Validation

- Checking for missing data and consistency of identification variables (use of reference tables).
- Duplicity detection and protocols per record.
- Consistency checks on each variable, this is determined against their attributes

2. Homologation, standardization and coding

- The standardization of the received administrative record is carried out to adapt it into a standard structure and to the codification of the variables according to the established reference tables.

4. Definition of Statistical Unit

5. Sustitution and integration GEIH-Admin. Records

- Matching of GEIH information with Admin. Records
- GEIH-Admin Records match consistency tests
- Substitution of information

Más Familias en Acción

GEIH and Administrative Records Match



El futuro
es de todos

Gobierno
de Colombia

Module M. Other income

Allowances flow of questions

During the LAST TWELVE MONTHS, did you receive money from other households, persons or institutions; money for interest, dividends, profits or severance pay?

Yes

C. Do you receive financial assistance from institutions in the country or outside the country?

Yes

C1. Was the financial assistance from government institutions?

Yes

¿Más Familias en Acción?

Yes?

When?

¿Jóvenes en Acción?

Yes?

When?

¿Colombia Mayor?

Yes?

When?

OTHER


Yes?

Which one?

How much?

Administrative Records and Más Familias en Acción (FA) - GEIH Match

Summary of the Deterministic match - Households and/or holders



Income Poverty Results 2020




El futuro
es de todos


Gobierno
de Colombia



Incidence of income poverty Main Domains (2012-2020)



Incidence of extreme income poverty Main Domains (2012-2020)



Poverty Measurement During COVID: Administrative Records as Contrast and Data Source Results 2020

November, 2021



El futuro
es de todos

Gobierno
de Colombia