

In-Vehicle Emergency Call Systems: From National Deployment to International Harmonization

Evgeni Meilikhov, PhD

ERA-GLONASS System: Four Years from Concept to Operation

services





Ensuring Interaction with emergency response


Development of the UNECE Regulation for Vehicle Emergency Call Systems



- The World Forum for Harmonization of Vehicle Regulations (WP 29) at the 159th session, March 2013: the Russian Federation announced its intent to propose a new UN Regulation governing emergency call systems.
- WP 29 at the 160th session, June 2013: an informal working group (IWG) was established under the Working Party on General Safety (GRSG) for developing the new UN Regulation for emergency call systems.
- **IWG on automatic emergency call systems** started its work chaired by the Russian Federation.
- The UN Regulation draft discussed at IWG meetings:
 - 08 10 October 2013 (Geneva)
 - 05 06 December 2013 (Paris)
 - 26 28 February 2014 (Moscow)
 - 28 30 April 2014 (Paris)
 - 02 04 September 2014 (Turin)
 - 18 20 November 2014 (Prague)
 - 25 27 February 2015 (Paris)
- The next IWG meeting to discuss the UN Regulation scheduled for 31 March – 2 April 2015 (Rüsselsheim)




eCall/ERA-GLONASS Standardization Challenge



- Cross-disciplinary standardization required
- Competency spread in different industries
- Regulated environment
- International standardization due to global nature of the car industry
- Interoperability requirements (vehicles cross borders)
- Adjacent areas / applications should be taken into account
- Customer perception matters


AECS Functions and Regulation Scope





Legacy Networks and System Infrastructure Define Minimum Requirements






Europe: 2G, in-band data transmission directly to PSAP

Russia: 2G & 3G, in-band and SMS data transmission, dedicated system infrastructure

Japan: 3G, packet data transmission, dedicated system infrastructure

Self-Consistent Components Benefit from 'Traditional' Approach





Hands-free audio: good chance to sync with P.emergency ITU-T recommendation Crash performance and resistance: well established crash testing methods (Reg 94 & 95) HMI requirements: defined in UNECE Reg. 121



Can Position Determination Requirements be Performance-Based? **Autonomous** Data transmission Wireless Hads-free Speaker performance mechanism and communication audio format Mic Back-up **Battery** GLONASS Galileo-**GPS** GMSC SMSC **(**((**4**))) **GNSS** AEC\$ NAD Receiver Logio Wireless infrastructure **Position** Syster Determination infrastructure Indicator **Automatic**

Triggering Signal

Crash

performance and

crash resistance

GNSS coverage is global, so no barrier for harmonization. However, test methods are technology-dependent.

Button

HMI

requirements

GNSS Requirements are Technology-Related



Horizontal position accuracy:

- Open sky conditions shall not exceed 15 m
 Urban canyons conditions shall not exceed 40 m
 PDOP not more than 2.5 and 4 respectively
 95% of the measurements done
 Speed up to 140 km/h

Sensitivity:

- Acquisition: at least minus 144 dBm Tracking: at least minus 155 dBm Reacquisition: at least minus 150 dBm

- Time to first fix not to exceed:
- 60 sec for signal level down to minus 130 dBm 300 sec for signal level down to minus 140 dBm
- Re-acquisition time after block out of 60 sec not to exceed:
- 20 sec at signal level down to minus 130 dBm

AECS Regulation:


First Attempt to Regulate Networked Car



- Connected Car technologies are rapidly developing
 - V2V
 - V2I
 - Driving automation
- Standalone performance criteria are insufficient
 - Selected technologies must be supported
 - Compatibility with infrastructure is required
 - Focus on performance in cooperative systems
- Non-functional criteria matter
 - Security
 - Privacy
 - Data integrity and reliability
 - Driver distraction

Regulatory Framework for Networked Car





Can the Networked Car be regulated as a network element?



Thank you

eem@glonassunion.ru